

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19747-00-00
Spot: NENENWNW Sec/Twnshp/Rge: 33-25S-5E
5167 feet from S Section Line, 4066 feet from E Section Line
Lease Name: PIERPOINT A Well #: 100 W
County: BUTLER Total Vertical Depth: 2052 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	52		
PROD	4.5	2050		140 SX
SURF	8.625	659		420 SX

Well Type: EOR UIC Docket No: E09803.25 Date/Time to Plug: 07/25/2013 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2013 10:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1250', TAGGED CEMENT PLUG. W/TBG @ 1247', CONSOLIDATED WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 10:00 AM, CONSOLIDATED CEMENT TICKET #43601. TOPPED WELL BACK TO SURFACE W/10 SXS.

Perfs:

Top	Bot	Thru	Comments
1985	1997		
1967	1977		
1684	1694		
1668	1672		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 13 2013

Remarks: E-09803 / CEMENT @ SURFACE ON BACKSIDE / COMPLIANCE/10 YEAR RULE

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
10/20/13 (TECHNICIAN)
cc to MIC 8/19/13

JK