

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22547-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 3-21S-11W
4355 feet from S Section Line, 2245 feet from E Section Line
Lease Name: SNIDER Well #: 1-D
County: STAFFORD Total Vertical Depth: 3410 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PLG	4.5	3250		
PROD	4.5	3409	1600	WITH 175 SX CMT
SURF	8.625	254		WITH 175 SX CMT

Well Type: EOR UIC Docket No: E25624.1 Date/Time to Plug: 08/23/2013 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SAND BOTTOM TO 3050' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS
Date/Time Plugging Completed: 08/23/2013 3:10 PM

Witness Type: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3050' WITH 4 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 610' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 32' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3210	3220		
3158	3163		
3126	3130		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 04 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Richard W. Lacey
cc to UIC 9/04/13 (TECHNICIAN)

RECEIVED

AUG 29 2013

KCC DODGE CITY