

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21821-00-00
Spot: NWSESW Sec/Twnshp/Rge: 31-18S-23W
1013 feet from S Section Line, 3645 feet from E Section Line
Lease Name: SCHNIEPP Well #: 1
County: NESS Total Vertical Depth: 4285 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4285	0	WITH 125 SX CMT
SURF	8.625	604		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2013 8:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: ERIK HAGNS Company: VINCENT OIL Phone: (620) 388-6143

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMO 40 SX CMT & 15 SX GEL. PULL TBG TO 1400' & CIRCULATE CMT. TIE ONTO BACKSIDE & PUMP UNTIL PRESSURED UP TO 500#.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2013 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN TBG TO 4180' & PUMP 15 SX GEL & 40 SX CMT WITH 100# HULLS. PULL TBG TO 1412' & PUMPED 160 SX CMT. CMT CIRCULATED TO SURFACE. PULL TBG & TIED ONTO BACKSIDE. PUMPED 10 SX CMT. PRESSURED TO 500# & HELD. TOPPED OFF CASING WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4258	4260		
4256	4258		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 07 2013

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

Signed Michael Maier
10/21/13 (TECHNICIAN)

RECEIVED

AUG - 2 2013

KCC DODGE CITY