

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23666-00-00
Spot: W2SESENE Sec/Twnshp/Rge: 35-25S-4E
2310 feet from N Section Line, 600 feet from E Section Line
Lease Name: SHARPSTEEN Well #: 1
County: BUTLER Total Vertical Depth: 2500 feet

Operator License No.: 33617
Op Name: WILSON PRODUCTION COMPANY, INC
Address: 46601 837TH RD
BURWELL, NE 68823

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2050		
CIBP	4.5	2400		
PROD	4.5	2491		200 SX
SURF	8.625	261		150 SX
T1	2.375	2400		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/08/2013 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: DAVE CORNISH Company: WILSON PRODUCTION CO Phone: (316) 259-7042

Proposed Plugging Method: AS PER KCC RULE & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/08/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 1910', RIH W/TBG @ 1600', CONSOLIDATED MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. RIH W/1" TBG ON BACKSIDE 4 1/2" CASING @ 350', CONSOLIDATED MIXED & PUMPED 90 SXS CLASS A COMMON TO SURFACE. LAYED DOWN TBG. RIH W/1" TBG ON INSIDE OF 4 1/2" CASING @ 180', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 70 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #42876.

Perfs:

Top	Bot	Thru	Comments
2412	2414	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: WIRELINE & BAILOR LEFT IN HOLE @ 1610' - 180'

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
10/20/13 (TECHNICIAN)