

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23256-00-00  
Spot: SWNWSESE Sec/Twnshp/Rge: 28-33S-8E  
850 feet from S Section Line, 1162 feet from E Section Line  
Lease Name: BURNETT Well #: 3-A  
County: COWLEY Total Vertical Depth: 2407 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2362		500 SX
SURF	8.63	50		50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/07/2013 8:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/07/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2251', DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. RIH W/1" TBG ON BACKSIDE @ 100', CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TBG. RIH W/TBG ON INSIDE OF 4-1/2" CSG @ 504', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 48 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PA COMPLETE. CEMENT TICKET #38486.

Perfs:

Top	Bot	Thru	Comments
2290	2310		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

DUANE KRUEGER  
10/20/13 (TECHNICIAN)

132