

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23261-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 28-33S-8E
516 feet from S Section Line, 1480 feet from E Section Line
Lease Name: BURNETT Well #: 5
County: COWLEY Total Vertical Depth: 2350 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2350		450 SX
SURF	8.63	51		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/03/2013 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/06/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2260', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. RIH W/1" TBG ON BACKSIDE @ 110', CONSOLIDATED MIXED & PUMPED 48 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TBG. RIH W/TBG ON INSIDE OF 4 1/2" CSG @ 504', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. TOPPED WELL BACK TO SURFACE W/5 SXS. PA COMPLETE. CEMENT TICKET #38360.

Perfs:

Top	Bot	Thru	Comments
2310	2316	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
10/24/13 (TECHNICIAN)