

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20473-00-00  
Spot: NWNWSEW Sec/Twnshp/Rge: 21-34S-43W  
1407 feet from N Section Line, 1463 feet from W Section Line  
Lease Name: INTERSTATE Well #: 14-21  
County: MORTON Total Vertical Depth: 1340 feet

Operator License No.: 33136  
Op Name: ANADARKO E & P ONSHORE LLC  
Address: PO BOX 1330  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1131		WITH 15 SX CMT
PROD	4.5	1339	0	WITH 500 SX CMT
SURF	8.625	370		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/03/2013 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 1131' WITH 15 SX CMT. RTIH TO 420' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/03/2013 6:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 1131' WITH 15 SX CMT. PULL TBG TO 420' & PUMP 30 SX CMT. CMT CIRCULATED TO SURFACE. PUMP 15 SX CMT AT 300# DOWN BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
1181	1215		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Kenny Sullivan  
10/03/13  
(TECHNICIAN)  
RECEIVED  
KANSAS CORPORATION COMMISSION

RECEIVED  
OCT - 9 2013  
KCC DODGE CITY

OCT 10 2013  
CONSERVATION DIVISION  
WICHITA, KS