

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21481-00-00
Spot: SESENWNE Sec/Twnshp/Rge: 5-34S-41W
1240 feet from N Section Line, 1360 feet from E Section Line
Lease Name: USA WACKER H Well #: 2H
County: MORTON Total Vertical Depth: 2410 feet

Operator License No.: 33136
Op Name: ANADARKO E & P ONSHORE LLC
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2080		WITH 15 SX CMT
PROD	5.5	2388	0	WITH 240 SX CMT
SURF	8.625	460		WITH 180 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/30/2013 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2080' WITH 15 SX CMT. PLUG AT 1230' WITH 30 SX CMT. PLUG AT 510' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2013 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2080' WITH 15 SX CMT. 1ST PLUG AT 1230' WITH 30 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. CMT CIRCULATED TO SURFACE. TOPPED OFF WITH 15 SX CMT. PRESSURED THE BACKSIDE TO 300# WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2130	2142		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.
Plugged through: TBG

District: 01

RECEIVED
OCT - 7 2013
KCC DODGE CITY

Signed Eric MacLaren
10/25/13 (TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION

OCT 10 2013
CONSERVATION DIVISION
WICHITA, KS

[Handwritten signature]