

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01087-00-01
Spot: N2SWNESE Sec/Twnshp/Rge: 12-34S-13W
1700 feet from S Section Line, 990 feet from E Section Line
Lease Name: J V COOK B Well #: 1
County: BARBER Total Vertical Depth: 4892 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 300 W DOUGLAS AVE, STE 410
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4360		WITH 2 SX CMT
CIBP		4821		
CIBP		4878		
PROD	5.5	4800	0	WITH 300 SX CMT
SURF	8.625	252		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/25/2013 12:00 PM

Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: PRESTON DREILING Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 4360' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN

Witness Type: NONE

Date/Time Plugging Completed: 09/25/2013 5:00 PM

KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

****DID NOT PULL CASING & SPOT PLUGS DUE TO SHALLOW CASING SQUEEZE.****
SET CIBP @ 4360' & 2 SX CMT. PERFORATE 5 1/2" CASING @ 600'. RUN TBG IN & CIRCULATED 5 1/2" CASING TO SURFACE WITH 75 SX CMT. PRESSURE UP ON PERFS TO 300#. UNABLE TO ESTABLISH CIRCULATION DUE TO SQUEEZE JOB. LAID TBG DOWN. TOP OFF 5 1/2" CASING WITH 125 SX CMT. PUMED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 10 SX CMT. LOADED PRESSURE UP TO 200#.

Perfs:

Top	Bot	Thru	Comments
4835	4867		
4577	4592		
4412	4432		

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 10 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

OCT -7 2013

KCC DODGE CITY

Signed

[Handwritten Signature]
10/25/13 (TECHNICIAN)

[Handwritten Initials]