

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25337-00-00
Spot: SWNWSENE Sec/Twnshp/Rge: 17-20S-21W
1971 feet from N Section Line, 1035 feet from E Section Line
Lease Name: PRAIRIE FARMS - HARRIS Well #: 1
County: NESS Total Vertical Depth: 4650 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 300 W DOUGLAS AVE, STE 410
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4360		WITH 2 SX CMT
CIBP		4618		
PC		1453		CEMENTED WITH 130 SX CMT. 15 SX CMT CIRCULATED TO PIT.
PROD	5.5	4641	0	WITH 140 SX CMT
SURF	8.625	264		WITH 2300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2013 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PRESTON DREILING Company: ANDERSON ENERGY Phone: (785) 639-2099

Proposed Plugging Method: SET CIBP @ 4360' WITH 2 SX CMT. RUN TBG TO 1500' & CIRCULATE CMT. CHECK BACKSIDE WITH 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/23/2013 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4360' WITH 2 SX CMT. RAN TBG TO 1554' & PUMPED 180 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4412	4417		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 10 2013

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

RECEIVED
OCT -7 2013

Signed Michael Maier
10/25/13 (TECHNICIAN)

District: 01

KCC DODGE CITY

BM