

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20721-00-00
Spot: N2NWSWNW Sec/Twnshp/Rge: 9-2S-19W
1500 feet from N Section Line, 330 feet from W Section Line
Lease Name: KENNETH Well #: 1
County: PHILLIPS Total Vertical Depth: 3686 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		175 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/23/2013 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TONY Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2415

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 09/23/2013 8:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report: _____ Perfs: _____

1st plug @1840 w/25 sx
2nd plug @1275 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED
Plugged through: DP

District: 04

Signed Case Morris
10/25/13 (TECHNICIAN)

SEP 25 2013

RECEIVED KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 02 2013

CONSERVATION DIVISION
WICHITA, KS