

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-20994-00-00  
Spot: NWNW Sec/Twnshp/Rge: 1-26S-3E  
4620 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: WARNER Well #: 1  
County: BUTLER Total Vertical Depth: 2710 feet

Operator License No.: 32753  
Op Name: CARAGEANNIS, PAUL C. DBA SEED GR  
Address: PO BOX 771189  
WICHITA, KS 67277

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2708		125 SX
SURF	8.625	170		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2013 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: PULL TUBING FROM WELL. RUN TO BOTTOM & CEMENT BACK TO 2610. PERFORATE 4 1/2" AT 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/06/2013 10:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

9/4//13/- QWS TRIPPED OUT 76 JOINTS OF TUBING, WITH A TALLY OF 2,368.31' FOUND TUBING PARTED ON 76TH JOINT. WILL GET OVERSHOT FROM KANSAS FISHING TOOLS. 9/5/13 - QWS TRIPPED IN WITH OVERSHOT, AND COULD NTO GET OVERSHOT PAST 100' INSIDE THE 4 1/2" CASING. DECISION MADE TO TRIP TUBING BACK TO TOP OF FISH AND SPOT BOTTOM PLUG. TAGGED BOTTOM PLUG AT 2010'. 9/6/13 - EXCEL WIRELINE PERFORATED 4 1/2" CASING AT 250'. TRIPPED TUBING TO 250' AND CIRCUALTED 80 SX 60/40 CEMENT TO SURFACE. TOPPED OFF WITH 15 SX.

Perfs:

Top	Bot	Thru	Comments
2668	2674		
2262	2265		KANSAS CITY

Remarks: FEE FUND CONTROL #20130088-001. THIS WELL WAS PLUGGED UNDER COMMISSION ORDER DOCKET NO. 12-CONS-198-CSHO.

Plugged through: TBG

District: 02

Signed Jeff Klock, District Supervisor  
RECEIVED  
KANSAS CORPORATION COMMISSION (TECHNICIAN)  
OCT 09 2013  
10/25/13  
CONSERVATION DIVISION  
WICHITA, KS