

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-10016-00-00
Spot: SWNWNWNE Sec/Twnshp/Rge: 18-30S-8W
4909 feet from S Section Line, 2395 feet from E Section Line
Lease Name: MESSENGER D Well #: 1
County: KINGMAN Total Vertical Depth: 4294 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4716		150 SX
SURF	8.625	257		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2013 4:00 PM
Plug Co. License No.: _____ Plug Co. Name: _____
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING, INC. Phone: (620) 277-0803

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/27/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP SET AT 4140' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1721' PULLED CASING. RAN TUBING INTO 1376' SPOTTED 35 SX CEMENT. PULLED TUBING TO 844' SPOTTED 35 SX CEMENT. PULLED TUBING TO 456' CIRCULATED TO SURFACE WITH 180 SXS, AFTER PULLING TUBING CEMENT FELL BACK 100+ FEET. ADDED ANOTHER 60 SX CEMENT ON TOP OFF.

Perfs:

Top	Bot	Thru	Comments
4258	4265		
4242	4250		
4238	4243		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 04 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING OUT OF MEDICINE LODGE, -- PLUGGED DUE TO DENIED TA OVER 10 YEARS

Plugged through: TBG

District: 02

Signed B. J. Hope
10/25/13 (TECHNICIAN)