

1 030343

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,717-0000 *R* ✓
100' W of SE/4 SE/4, SEC. 1, T 19 S, R 22 W/EX

660 feet from (S) section line
760 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Schaben Well # 1-1

Operator: W. L. Kirkman, Inc.

County Ness

Name & Address Box 982

Well Total Depth 4355 *141.59* feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 13 Month: December Year: 19 84

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" set at 4354' PBSD 4340' Perfs at 4298-4302'

1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 160 sx cement.

Plugging Proposal Received by Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 pm Day: 13 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4354' PBSD 4340' Perfs at 4298-4302'

1st plug sanded back to 4250' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls,

hulls, released 8 5/8" rubber plug and pumped 160 sx cement.

Remarks: Recovered 2000' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

(I did not) observe this plugging.

Signed Steve Dumont
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
DEC 13 1984

DATE 12-26-84
6165