

1 040332

10-9

10403-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-01,018-
C SW SW, SEC. 26, T 30 S, R 14 W/E
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9533

Lease Name Lambert Well # 1

Operator: Fairchild Exploration
Name & Address Route 3
Kingman, KS 67068

County Barber 131.62
Well Total Depth 4050 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 9 Month: 10 Year: 19 89

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4038' PBTD 4000' Perfs at 3918-28'

1st plug pump 200 lbs. hulls and 30 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION OCT 12 1989 10-12-89

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 9 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 100 lbs. hulls and 30 sx cement (Titan).

8/9/89 Pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, and started to

mix cement. Fluid surfaced at several places outside of cellar (maximum pressure 500 psi).

Tried to rag off hole in surface pipe, unsuccessful. Allied cementing.

10/9/89 Moved rig on to wash down and plug through tubing. Hole full of gel.

Spotted plugs through 2 3/8" tubing: 1st plug at 700' with 50 sx cement, 2nd plug at 300' with 40 sx cement, 3rd plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 4 1/2" casing.

If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-13-89

Signed Stephen J. Pfeiffer
(TECHNICIAN) RAWL

INV. NO. 26138