

RECEIVED  
STATE CORPORATION COMMISSION

4-19  
2-040635

74  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

AUG 19 1991  
CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER: 15-077-21,239-00-00

NE NE SE, SECTION 11 TOWNSHIP 34 RANGE 6W

OPERATOR LICENSE # 30672 2310 FEET FROM S SECTION LINE  
330 FEET FROM E SECTION LINE

OPERATOR Carl E. Gungoll Explor. Inc.  
NAME & 14000 Quail Springs Pkwy., #220  
ADDRESS Oklahoma City, OK 73134

LEASE NAME: Faye #1-11

COUNTY: Harper 162.50

WELL TOTAL DEPTH: 5000'

PIPE: 10-3/4" @ 40'

SURFACE CASING: 8-5/8" @ 300'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Lobo Drilling  
ADDRESS: Great Bend, KS LICENSE: 5864

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: \_\_\_\_\_ MONTH: \_\_\_\_\_ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Ervin Neighbors

COMPANY NAME: Lobo Drilling PHONE: \_\_\_\_\_  
WERE: 35 sx @ 950' - 35 sx @ 650' - 35 sx @ 350' - 25 sx @ 60' - 10 sx in rat hole - 10 sx in mouse hole.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 06:30 DAY: 19 MONTH: 4 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Drill pipe was run open-ended to 950 where 35 sx cmt spotted - 35 sx cmt plug also spotted 650' & 350' thru drillpipe as it was pulled from wellbore - 25 sx plug used to circ cmt to surf from 60' - rat & mouse were each circ with 10 sx cmt.

REMARKS: Allied Cementing 40/60 poz 2% gel

I DID NOT OBSERVE THIS PLUGGING.

INVOICED  
DATE 8-28-91  
MIL NO 32851

Steve Van Gieson  
Steve Van Gieson (AGENT)

DW