

6-6-96

2-040874

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-077-21,223-00-00

75' S NE NW SW, SECTION 4 TOWNSHIP 34 RANGE 6W

OPERATOR LICENSE # 5399 2235 FEET FROM S SECTION LINE
OPERATOR AMERICAN ENERGIES CORPORATION 4290 FEET FROM E SECTION LINE
NAME & 155 NORTH MARKET #710
ADDRESS WICHITA, KS 67202
LEASE NAME: BOLMAN "F" #1
COUNTY: HARPER 149.56
WELL TOTAL DEPTH: 4602' PB 4598'
PIPE: _____
SURFACE CASING: 8 5/8" @ 283'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: ALAN DEGOOD

COMPANY NAME: AMERICAN ENERGIES CORPORATION PHONE: _____

WERE: 4 1/2" AT 4598'
PERFS 4505' - 4512'
35 SACKS AT 1150'
35 SACKS AT 690'
CIRCULATE CEMENT 320' - 0'

PLUGGING PROPOSAL RECEIVED BY: DISTRICT #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { X } NONE { _____ }

COMPLETED: HOUR: 15:00 DAY: 6 MONTH: 6 YEAR: 1996

ACTUAL PLUGGING REPORT: SAND WAS USED TO COVER THE PERFS FROM 4598' TO 4450' AND CAPPED WITH 4 SACKS OF CEMENT. THE 4 1/2" WAS RECOVERED FROM 4000' AND PULLED TO 1155' WHERE 35 SACKS WAS SPOTTED. PIPE PULLED TO 683', 35 SACKS SPOTTED. PIPE PULLED TO 315' AND CEMENT WAS CIRCULATED TO SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

REMARKS: 60/40 POZ 4% GEL ALLIED MAR 06 1997

CONSERVATION DIVISION
WICHITA, KS
I DID OBSERVE THIS PLUGGING.
Steve Van Gieson
STEVE VAN GIESON

INVOICED

DATE 3-6-97

INV. NO. 47705

6-6-96