

1041338

TO: STATE CORPORATION COMMISSION

2-5

API NUMBER 15-007-21,381-00-00  
NW NE SEC. 30, T 32 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME PALMER WELL # C-1

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER 149.99

OPERATOR LICENSE # 5506 WELL TOTAL DEPTH 4615 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 4615' WITH 150 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 320' WITH 300 SX

ADDRESS MEDICINE LODGE, KS 67104

ABANDONED OIL WELL X GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 04 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 4529-31, 4553-60, CIBP @ 4450, PERFS @ 4298-4304, CIBP @ 4250, PERFS @ 4056 TO 60 & 3962-72.

CIBP AT 3930' AND 2 SX CEMENT DOWN 8 5/8" CASING. PUMP 300# HULLS, 10 SX GEL, 50 SX CEMENT,

10 SX GEL, 100# HULLS, 8 5/8" WIPER PLUG AND 100 SX CEMENT. TOP OFF SURFACE IN 24 HOURS.

RECEIVED

KANSAS CORPORATION COMMISSION

FEB 10 1999

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 05 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP @ 3915'. (NO CEMENT ON TOP OF CIBP, UNABLE TO GET DUMP BAILER THRU

TIGHT SPOT IN 4 1/2" CASING AT 860'.

SPOT PLUGS THROUGH 2 3/8" TUBING. SEE ATTACHED PAGE.

REMARKS: USED 60/40 POZMIX 6% GEL & AFC CEMENT BY ALLIED. RECOVERED 810' OF 4 1/2" CASING. IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

I (DID) OBSERVE THIS PLUGGING.

DATE 2-17-99

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-2/3

INV. NO. 60640