

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24054-00-00
Spot: E2NENW Sec/Twnshp/Rge: 26-19S-22W
760 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: DORSA Well Number: 2
County: NESS Total Vertical Depth: 4395 feet

Operator License No.: 8996
Op Name: MID-CONTINENT RESOURCES, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 311 WITH 180 SX CMT
Production: Size 5.5 feet: 4390 WITH 100 SX CMT
Liner: Size feet: 8142.84

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/05/2001 10:10 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: SAND BACK. PORT COLLAR AT 1490'. PLUG THROUGH CASING. 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 320' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 10/05/2001 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4333'. PACKER WAS LEFT IN HOLE AT 4333'. SANDED TO 4250' WITH 4 SX CMT. 1ST PLUG AT 1515' WITH 10 SX GEL - 50 SX CMT - 2 SX GEL. 2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 320' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GLE BY SWIFT SERVICES. RECOVERED 1995' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Michael Maier
(TECHNICIAN)

RECEIVED

OCT 11 2001
10-11-01
KCC WICHITA

INVOICED

DATE 10-11-01
INV. NO. 2002060791

OCT 08 2001

MD

Form CP 2/3