

1 120937

7-12

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 7/24/68  
150' NE of  
NE NE SE, SEC. 26, T 19 S, R 22 W/X  
App. 2385 feet from S section line  
App. 255 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010  
Operator: Knighton Oil Co., Inc.  
Name & Address: 710 Petroleum Bldg.,  
Wichita, KS 67202

Lease Name Gillig Well # 1  
County Ness  
Well Total Depth 4398 142.93 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 489

Abandoned Oil Well \_\_\_\_\_ X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Knighton Oil Co. License Number 5010  
Address 710 Petroleum Bldg., Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 12 Month: 7 Year: 19 94

Plugging proposal received from Carl Gilpin  
(company name) Knighton Oil Co. (phone) 316-264-7918

Perfs: 4 1/2" at 4396' w/100 sx cement, PBSD 4393', Perfs at 4382-88'  
1st plug pump 2 sx hulls and 20' sx cement and gel spacer to between Anhydrite & Permian perfs,  
2nd plug perforate at 800' and pump capacity of 4 1/2" to 800' plus 80 sx cement,  
3rd plug pump 200. sx cement down annulus.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:20 a.m. Day: 12 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx cement and displaced with water to 4300',

2nd plug perforated 4 1/2" casing at 800-802' and circulated 4 1/2" X 8 5/8" annulus 260 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1994  
7-15-94  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 7-27-94  
WV. NO. 40883

Signed \_\_\_\_\_ (TECHNICIAN)