

To: 1 070006
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,846-0000 *R*
NW SE NE, SEC. 24, T 19 S, R 22 W/E
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5804

Lease Name Wegele Well # 1

Operator: Dreiling Ltd. of Colorado
Name & Address 410 -17th St., Suite 1140
Denver, CO 80202

County Ness 141.05
Well Total Depth 4340 (Mississippi) feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 412 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor C & R Drilling Co. License Number 5815

Address Box 57, Hays, KS 67601

Company to plug at: Hour: 6:30 pm Day: 29 Month: June Year: 19 85

Plugging proposal received from Monty Goodrow

(company name) C & R Dilling Co. (phone) 913-628-3699

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1452' Elevation 2205'

1st plug at 1440' with 50 sx cement

2nd plug at 720' with 60 sx cement

3rd plug at 420' with 50 sx cement

4th plug solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 8:30 pm Day: 29 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement, 2nd plug at 720' with 60 sx

cement, 3rd plug at 420' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(if additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 7-11-85

INV. NO. 8852

Signed Dan Gobler (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 7-9-85

CONSERVATION DIVISION Wichita Kansas