

1 050858

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,080 -0000SE NE SE SEC. 27, T 19 S, R 22 W/E1650 feet from S section line330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767Lease Name Glaves Well # 1Operator: Ritchie Exploration, Inc.County Ness

Name &

Address 125 N. Market, Suite 1000Well Total Depth 4406 feetWichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 400Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033Address 250 N. Water, Suite 300, Wichita, KS 67202Company to plug at: Hour: 1 a.m. Day: 13 Month: 12 Year: 1986Plugging proposal received from Rodney Farr(company name) Murfin Drilling Company (phone) 303-775-9454were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2259'
Anhydrite 1540'1st plug at base Anhydrite with 50 sx cement, 2nd plug at 780' with 75 sx cement,3rd plug at 340' with 50 sx cement, 4th plug at 40' with 10 sx cement,5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10
sx cement.Plugging Proposal Received by Richard Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All _____ Part _____ None XOperations Completed: Hour: 4:45 a.m. Day: 13 Month: 12 Year: 1986ACTUAL PLUGGING REPORT 1st plug at 1544' with 50 sx cement,2nd plug at 780' with 75 sx cement,3rd plug at 430' with 50 sx cement,4th plug at 40' with 10 sx cement,5th plug to circulate rathole with 15 sx cement,6th plug to circulate mousehole with 10 sx cement.Remarks: Used 60/40 Pozmix 6% gel by Allied.(If additional description is necessary, use BACK of this form.)I did not observe this plugging.DATE 12-16-86Signed Richard W. Lacey
(TECHNICIAN)INV. NO. 15646

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 13, 1986
month day yearAPI Number 15- 135-23,080-0000OPERATOR: License # 4767
Name Ritchie Exploration, Inc.
Address 125 N. Market, Suite 1000
City/State/Zip Wichita, Kansas 67202
Contact Person Leah Ann Kasten
Phone 316/267-4375SE NE SE Sec. 27 Twp. 19 S, Rg. 22 East
1.650 Ft. from South Line of Section
330 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County NessLease Name Glaves Well # 1Ground surface elevation est. 2259 feet MSLDomestic well within 330 feet: yes X noMunicipal well within one mile: yes X noDepth to bottom of fresh water 420-200Depth to bottom of usable water 725Surface pipe by Alternate: 1 2XSurface pipe planned to be set 320Conductor pipe required noneProjected Total Depth 4500 feetFormation MississippianCONTRACTOR: License # 6033
Name Murfin Drilling Co.
City/State Wichita, KansasWell Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext. Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 11/26/86 Signature of Operator or Agent Leah Ann Kasten Title Geologist No

For KCC Use:

Conductor Pipe Required 210 feet; Minimum Surface Pipe Required 40 feet per Alt. 40This Authorization Expires 6-1-87 Approved By 12-1-86 fen/ku

Set 320' of 8 5/8

SE NE SE Sec. 27 Twp. 19 S, Rg. 22 East
X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>1500</u> <u>Anhydrite</u>	feet depth with <u>50</u>	sxs of <u>cement</u>
2nd plug @ <u>780</u>	feet depth with <u>75</u>	sxs of <u>"</u>
3rd plug @ <u>340</u>	feet depth with <u>50</u>	sxs of <u>"</u>
4th plug @ <u>40</u>	feet depth with <u>10</u>	sxs of <u>"</u>
5th plug @ <u>10</u>	feet depth with <u>15</u>	sxs of <u>"</u>
(2) Rathole with <u>10</u>	sxs	(b) Mousehole with <u>10</u> sxs

PUSHER Radney FarrTD 4400 FORMATION 400SURFACE PIPE 8 5/8 @ 400ANHYDRITE 1540 ELEVATION 2259STARTING TIME & DATE 1:00 am 12-17-86COMPLETION TIME & DATE 4:45 am 12-17-861st PLUG @ 1544 FT. W/ 50 SX2nd PLUG @ 780 FT. W/ 75 SX3rd PLUG @ 430 FT. W/ 50 SX4th PLUG @ 40 FT. W/ 10 SXRAT HOLE CIRCULATED W/ 15 SXMOUSE HOLE CIRCULATED W/ 10 SXWATER WELL PLUGGED W/ 10 SXCEMENT COMPANY AlliedTECHNICIAN Lacey60/40 6/4091

STATE CORPORATION COMMISSION

DEC 16 1986

CONSERVATION DIVISION
Wichita, Kansas