

195
2-010090 R

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

3-17

API NUMBER: 15-077-21,298-00-00

NE SE NW SE, SEC 19, T 34 S, R 5W

OPERATOR LICENSE # 31713

1815 FEET FROM S SECTION LINE

OPERATOR: Crescent Exploration LLC

1445 FEET FROM E SECTION LINE

NAME & 5600 N. May, Suite 300

LEASE NAME: WENCH WELL # 19-A

ADDRESS: Oklahoma City, OK 73112

COUNTY: Harper

WELL TOTAL DEPTH: 3750' 121.87

CONDUCTOR PIPE: @

SURFACE CASING: 8 5/8" @ 269'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A X

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR Duke Drilling Co., Inc.

ADDRESS: 310 W. Central, Suite 117, Wichita KS 67206 LICENSE: 5929

COMPANY TO PLUG AT: HOUR: 12:15 DAY: 17 MONTH: March YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM Joe Levingston

COMPANY NAME: Duke Drilling Co., I PHONE: 316-267-1331

WERE: Fill hole with heavy mud. Spot plugs through drill pipe. Spot 35 sacks cement at 950', spot 35 sacks cement at 319', spot 20 sacks cement at 60', fill rathole with 15 sacks cement, and fill mouse hole with 10 sacks cement.

PLUGGING PROPOSAL RECEIVED BY:

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { x }

COMPLETED: HOUR: 13:00 DAY: 17 MONTH: March YEAR: 1996

ACTUAL PLUGGING REPORT: Filled hole with heavy mud. Spotted cement through drill pipe. Spotted 35 sacks cement at 950', spotted 35 sacks cement at 319', spotted 20 sacks cement at 60', filled rathole with 15 sacks cement, and filled mousehole, with 10 sacks cement.

KANSAS CORPORATION COMMISSION

REMARKS: Used 60/40 pozmix with 6% gel by Allied - Invoice #3913

APR 09 1996

I DID NOT OBSERVE THIS PLUGGING.

CONSERVATION DIVISION
WICHITA, KS

Michael R. Wilson
Michael R. Wilson

AGENT

INVOICED

DATE: 4-10-96

INV. NO. 45173

FORM CP-2/3
REV. 3/90

DW