

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21395-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 35-33S-8W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: PROUSE L Well Number: 1-35
County: HARPER Total Vertical Depth: 4739 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: 154.02
Surface Casing: Size 8.625 feet: 263 180 SX CMT
Production: Size 5.5 feet: 4737 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/20/2002 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MICHAEL WILSON Company: KCC Phone: (316) 337-6231

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 08/20/2002 4:45 PM

Witness Type: Plugging Operations Partially Witnessed
KCC Agent: DAVE WERTZ

Actual Plugging Report:

Sand back to 4600' cap w/5sxs. Shot casing off @3430'. Pulled to 1350' spotted 35sxs thru casing. Well started flowing back all 35sxs in cellar. Pumped 80bbbls on 9lbs mud. Spotted 35sxs. Pulled to 310' pumped 95sxs circulated.

RECEIVED
KCC DISTRICT #2
SEP 18 2002
WICHITA, KS

Remarks: RECOVERED 3430' OF 5 1/2". ACID SERVICE # 5083. 60/40 POZ., 4% GEL. 200SXS.

Plugged through: CSG

District: 02

Signed

Dave Wertz
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-19-02

WV. NO. 2003060539