

2 040131

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-077-21024-00-00

NEW 1/4 SEC. 34, T. 33 S, R. 9 W

4950 feet from N/S section line

2970 feet from section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Morrow Well # 2-34

Operator: Texas Energies Inc.

County Harper 154.38

Name & Address P.O. Box 947

Well Total Depth 4750 feet

Pratt Ks 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P.O. Box 329 Pratt Ks 67124

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Dennis Petz

(company name) Wheatstate Oilfield Services (phone) \_\_\_\_\_

were: 35 SX 500'

50 SX 300'

15 SX 40'

10 SX RH

10 SX RH

RECEIVED  
STATE CORPORATION COMMISSION

NOV 26 1984

Plugging Proposal Received by \_\_\_\_\_ CONSERVATION DIVISION  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 0745 Day: 31 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT Hole was filled with mud. Drill

pipe was run to 500' and 35 sacks of cement

was spotted at 500'. The Drill Pipe was pulled

to 300' and 50 sacks of cement was spotted. Drill

pipe was pulled from the end a bridge was set

at 40' and 15 sacks was spotted on the bridge.

10 sacks of cement was circulated thru Drill pipe

(If additional description is necessary, use BACK of this form.)

INVOICE (did not) observe this plugging.

Signed Stella Green  
(TECHNICIAN)

RO

DATE 12-4-84

INV. NO. 5783 8-31

DEC 07 1984

in the Rat hole and 10 sacks of cement was  
circulate in the mouse hole. By Sun  
Cementing (NL)

---

Called Texas Energies office to inquire about  
who was pushed on rig and called for  
plugging order, and who was cement company  
and the time of completion. I feel that  
from the looks of the plugging orders, the  
pusher called the Dodge City District office for  
orders and it was not relayed to the Wichita  
office.

Stell June