

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,700

LEASE NAME Schriock

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

SPOT LOCATION C NE NE

SEC. 10 TWP. 19 RGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 12-16-85

Plugging Completed 1-3-86

LEASE OPERATOR Sharon Resources, Inc.
c/o Sharp Engineering, Oil Operations
ADDRESS 708 One Main Place
Wichita, Ks. 67202

PHONE #(316)-721-2638 OPERATORS LICENSE NO. 9883

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4371'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	408'	None
				5-1/2"	4370'	2271.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 4250' and 5 sacks cement. Shot casing at 3100' and 3000'. and 2300'. Pulled 54 joints of 5-1/2" casing. Halliburton squeezed well with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 15 sacks gel, 1 sack hulls, released plug and pumped 125 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 750 psi and shutin 450 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Gt. Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 15th day of January, 1986



IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

RECEIVED
STATE CORPORATION COMMISSION

M. Leatherman
Notary Public

My Commission expires:

JAN 16 1986

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-82