

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 9 TWP. 31S RGE. 14W E/W
Location as in quarters or footage from lines:
C. of NE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Tomlinson Oil Co., Inc.
Lease Name McGarth #1 Well No. _____
Office Address Suite 1030, 200 W. Douglas, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6/18/81
Plugging completed 7/7/81
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 3110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				12-3/4	108	None
				8-5/8	807	None
				4 1/2"	3089	2264'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in. Found plug back at 2700'. Pulled 18 1/2" tension. Made shots at 2415, 2350,
2285 and 2250. Pulled a total of 68 joints. Squeezed hole with 15 sacks gel, 6 sacks
hulls and 10 sacks gel. Displaced with 175 sacks 50/50 pos 4% gel 3% cc.
Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1981

My Commission expires: 

Joan Kelso
Notary **RECEIVED**
STATE CORPORATION COMMISSION

JUL 10 1981
7-10-81
CONSERVATION DIVISION
Wichita, Kansas

15-007-20351-0000
WELL LOG

COMPANY Mahoney Drilling Company

SEC. 9 T. 31S R. 14W

FARM McGrath NO. 1


LOG. C NE/4

TOTAL DEPTH 3110

COUNTY Barber

COMM. 9-16-75 COMP. 9-27-75

CONTRACTOR DaMac Drilling Company, Inc.



CASING 8 5/8 set @ 807

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0	371	Surface clay, Sand, Shells
371	645	Red Bed & Shale
645	1565	Shale
1565	3110	Lime & Shale
	3110	RTD

Casing Record:

- 19/75 12 3/4" 35.99#/ft set at 108' w/ 150 sacks Portland w/ 3% c.c.
- 20/75 8 5/8" 20#/ft set at 807' w/ 350 sx light, 100 sx Portland, 2% c.c.
- 27/75 4 1/2" 10.5#/ft set at 3,089' w/ 75 sx Portland, 75 Poz, 2% gel

'RTD:

Perforated Top Cement @ 2800'

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1981
5-26-81
CONSERVATION DIVISION
Wichita, Kansas


Restorations:

- 10/6/75 2997'-2999' w/ ~~two~~ 4 Holes per foot - Plugged off w/ Bridge Plug @ 2955' 10/7/75
- 2900' - 2910 w/ Two Holes per foot - Currently open.

State of Kansas }
County of Barton } as

I, Martha J. McKown of DaMac Drilling Company, Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the McGrath No. 1 well.



Martha J. McKown

Subscribed and sworn to before me this 8th day of October 1975

My Commission Expires: 11-11-78

Donald Sloup
NOTARY PUBLIC