


15-807-18169-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Barber County, Sec. 9 Twp. 31 Rge. 14 (NW) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW SW  
Lease Owner J. M. Huber & Cities Service  
Lease Name Mills Well No. 1  
Office Address 916 S. Pine - Pratt, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 6-17-46 19.  
Application for plugging filed 1-7-52 19.  
Application for plugging approved 1-8-52 19.  
Plugging commenced 1-8-52 19.  
Plugging completed 1-12-52 19.

Reason for abandonment of well or producing formation  
Not profitable to produce

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough - Great Bend, Kans.

Producing formation Depth to top Bottom Total Depth of Well 4370 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				15 $\frac{1}{2}$ "	99'	None
				10"	792-	None
				5 $\frac{1}{2}$ "	4360	3206

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to ...feet for each plug set.

Set fresh water plug at 275' and cemented w/20 sacks  
Mudded hole to 35', set bridge and cemented w/10 sacks.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. M. Huber Corp.  
Address Box 460  
Pratt, Kansas

STATE OF KANSAS, COUNTY OF PRATT, SS.  
I, J. L. Kyler (employee of owner) or ~~Notary Public~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of February, 1952, 19.

My commission expires September 10, 1955

22-5133-s 9-48-10M

J. L. Kyler  
Notary Public.

2-29-52

PLUGGING  
FILE SEC 9-T-31 R 142  
BOOK PAGE 137 LINES 31

J. M. Huber & Cities Service Oil Co.  
Mills #1

NW SW SW  
Sec. 9-31S-14W  
Barber County, Kansas

Started: 5-20-46  
Completed: 6-17-46

CASING: 99' 15 1/2" With 150 sacks of cement  
792' 10" With 300 sacks of cement  
4360' 5 1/2" With 225 Sacks of cement

Sand	0	65
Red bed, shells	65	115
Red Bed	115	140
Red bed, shale	140	805
Shale, shells	805	1190
Salt, shale, shells	1190	1410
Shale, shells	1410	1680
Lime, shells, shale	1680	1860
Lime, shale	1860	1910
Shale, lime	1910	1965
Lime, shale	1965	2155
Broken lime	2155	2175
Lime	2175	2190
Broken lime, shale	2190	2300
Lime	2300	2350
Lime, shale	2350	2435
Lime, shale brks	2435	2535
Lime, shale	2535	3020
Brkn lime, shale	3020	3125
Broken lime	3125	3580
Lime, shale	3580	3715
Lime	3715	3735
Lime, shale	3735	3865
Lime	3865	3900
Brkn lime	3900	3975
Lime	3975	4060
Lime, shale	4060	4095
Lime	4095	4255
Lime, shale	4255	4320
Lime, shale strks	4320	4360
Dolomite	4360	4370

Total Depth

Tops:

Lansing	3756'
Cherty Congl.	4270'
Maquoketa	4334-60
Dolomite	4360-70

Loaded hole, drilled plug and cleaned out to 4370 TD.  
Ran tubing and unloaded hole by swabbing through tubing.  
Swabbed 2 to 2 1/2 BOPH. Treated with 500 gallons of acid.  
Flowed into tanks 150 barrels of oil in three hours.  
Flowed 68 Barrels Oil 1st hour  
45 Barrels 2nd hour  
38 Barrels 3rd hour

**PLUGGING**  
WJ SEC 9T-31R-14W  
PAGE 13 / LINE 31

2-29-52