


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 3 Twp. 31 Rge. 14 E/W
Location as "NE/CNW¹/SW¹" or footage from lines
C SE/4 SE/4
Lease Owner Raymond Oil Co., Inc.
Lease Name Nittler #2 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/28/78 _____ 19____
Plugging completed 7/6/78 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3924
Show depth and thickness of all water, oil and gas formations. 4165'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	816	none
				4 1/2"	3924	2427'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 3050' and set 5 sacks cement. Shot pipe at 2945', 2883', 2800', 2673', 2584', 2501',
2673', 2421', pulled 75 joints. Set rock bridge at 450' and ran 7 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1978

7-27-78

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

WALTER VOTH (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 78

My commission expires _____



Margaret Melcher
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Nittler #2
 C SE SE Sec 3-31S-14W
 Barber County, Kansas

Commenced: 12-7-77

Completed: 12-19-77

OPERATOR: MALLONEE-MAHONEY, INC.

Depth		Formation	Remarks
From	To		
0	45	Surface Clay-Red Rock	
45	256	Redbed-Shale	Ran 20 jts of 20# 8-5/8"
256	720	Shale-Shells	csg set @ 816' Cemented
720	1170	Shale	w/300 sks Howcolite 1/2#
1170	1700	Lime-Shale	Flocele per sack w/2% CC
1700	2460	Shale-Lime	+100 sks Common 3% CC
2460	2660	Lime	PD @ 7:45 a.m. 12-8-77
2660	2816	Lime-Shale	
2816	2973	Shale-Lime	
2973	3065	Lime-Shale	Ran 113 jts of 10 1/2# 4 1/2"
3065	3570	Lime-Shale	csg set @ 3924' Cemented
3570	4165	Lime	w/250 sks 50/50 Posmix
			10% Salt 12 1/2# Gilsonite
			PD @ 7:40 p.m. 12-19-77
	4165 - TD		

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 29th day of December, 1977.



Marjorie Hall
 MARJORIE HALL-NOTARY PUBLIC

My Commission expires November 29, 1979.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 19 1978
 6-19-78
 CONSERVATION DIVISION
 Wichita, Kansas