

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber Co. SEC. 3 TWP. 31S RGE. 14W E/W
Location as in quarters or footage from lines:
C of SW

Locate Well
correctly on above
Section Platt.

Lease Owner Tomlinson Oil Co., Inc.
Lease Name Nittler #1 Well No. _____
Office Address Suite 1030, 200 W. Douglas, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6/15/81
Plugging completed 7/7/81
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 3080'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	310	None
				4 1/2"	3060	2335'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in. Found plug back at 2590'. Pulled 19" tension. Made shots at 2555, 2420
and 2320'. Worked pipe free and pulled a total of 70 joints. Squeezed hole with
15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and displaced with
125 sacks 50/50 pos 4% gel 3% cc. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1981

My Commission expires: 

Joan Kelso
Notary **RECEIVED**
STATE CORPORATION COMMISSION
7-10-81
JUL 10 1981

CONSERVATION DIVISION
Wichita Kansas

15-007-20352-0000
WELL LOG

COMPANY Mahoney Drilling Company

SEC. 3 T. 31S R. 14W

FARM Nittler

NO. 1

LOG. C SW


TOTAL DEPTH 3080'

COUNTY Barber

COMM. 10-12-75

COMP. 10-12-75

CONTRACTOR DaMac Drilling Company, Inc.



CASING 8.5/8 set @ 310' w/ 300 SKS circ

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0	100	Surface Sand, Clay & Shells
100	320	Sand & Shale
320	918	Sand, Shale, Red Bed
918	1260	Shale
1260	3080	Shale & Lime
	3080	RTD

4 1/2" 10.5 CASING set @ 3060 ft w/ 150 SKS 2% gel
perf. 2958 - 2972' w/ 2 SPF.
perfs squeezed off. Top of cement @ 2800'

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1981
5-26-81
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } as

I, Martha J. McKown of DaMac Drilling Company, Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Nittler well.

DONALD SLOUP
STATE NOTARY PUBLIC
Barton County, Kansas
My Commission Expires
November 11, 1978

Martha J. McKown

Subscribed and sworn to before me this 22nd day of October 19 75

My Commission Expires: 11-11-78

Donald Sloup
NOTARY PUBLIC