

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1966
7-26-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Curley Brau of Edmiston Drilling Co. has this date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Ks.

Lease Name: Lake Well No. # 1

Location: C SW NW Sec. 25 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4862 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

236' of 8 5/8" surface pipe, cementt, circulated with 275 sacks. Fill hole with drilling mud to 230', 1st cementing plug, bridge with 1/2 sack hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sacks of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent