

15-007-00671-0000

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 7 1964

4-7-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Cal Roberts of Leben Drilling Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Company

Complete Address: 815 Union ^{NATIONAL} Center Bldg., Wichita, Kansas

Lease Name: Don Skinner Well No. # 1

Location: SE NE NE Sec. 8 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4634 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

281' of 8 5/8" surface pipe, cemented with 225 sacks. Fill hole with drilling mud to 275, 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent