

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1966
2-2-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Dunham of Aspen Drilling Company has this
date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Brooks Hall

Complete Address: 1704 Liberty Bank Bldg., Oklahoma City, Okla.

Lease Name: Shaft Well No. # 1

Location: App. NW NE SW Sec. 18 Twp. 31 Rge. 14 (E)(W) W

County Barber Total Depth 4754' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

912' of 8 5/8" surface pipe, cemented with 865 sacks. Fill hole
with drilling mud to 300', 1st cementing plug, bridge with hulls,
and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with hulls, and cement with 10 sacks
to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent