

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1966
4-8-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. C. E. Richardson of Amerada Petroleum Corp. has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: Amerada Petroleum Corporation

Complete Address: Box 197, Great Bend, Kansas

Lease Name: Grace Freeman Well No. # 1

Location: C SE SW Sec. 4 Twp. 31 Rge. 6 (E)(W)W

County Harper Total Depth 4450' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richardson was instructed to plug the well as follows:

248' of 8 5/8" surface pipe, cement circulated with 225 sacks.
Fill hole with drilling mud to 240', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving
Conservation Division Agent