

R

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 14 1976  
12-14-76  
CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -007-20274-0000

Operator's Full Name Sohio Petroleum Co

Complete Address Box 673 Russell, KS

Lease Name Mott Well No. 1

Location C NW/NW Sec. 24 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4608

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 4:00 PM Day 11 Month 12 Year 1976

The above well was plugged as follows:

213 ft 8 5/8 surface cemented with 175 sacks. 2976 ft 4 1/2 long string  
cemented with 250 sacks. Top perf. 2742 ft. Sand to 2675 ft, 4 sacks  
cement with bailer. Pulled 2000 ft 4 1/2. Set 10 ft rock bridge at  
200 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 12-15-76  
NO. 4313-W