

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Brooks Hall

Complete Address: 1704 Liberty Bank Bldg., Oklahoma City, Oklahoma

Lease Name Shaft Well No. # 1

Location NW NE SW Sec. 18 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth # 1 3303'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: This was a lost hole.

Plugging Contractor: Aspen Drilling Company

Address: Great Bend, Kansas License No.

Operation Completed: Hour 5:30 AM Day 8th Month Jan. Year 1966

The Above well was plugged as follows:

868' of 8 5/8" surface pipe, cemented. Fluid level in the hole was at  
265'. 1st cementing plug, bridged with hulls on fluid at 265', and  
cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with hulls on fluid at 40', and cemented with  
10 sacks to the base of the cellar. Rat hole bridged and cemented with  
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 1/11/66

INV. NO. 2561-W