

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasJAN 13 1966
1-13-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Brooks Hall

Complete Address: 1704 Liberty Bank Bldg., Oklahoma City, Oklahoma

Lease Name Shaft Well No. # 1

Location Approx. NW NE SW Sec. 18 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 915'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: This is the 2nd time a hole has been lost on this location. Rig will be skidded again.

Plugging Contractor: Aspen Drilling Company

Address: Box 783, Great Bend, Kansas License No.

Operation Completed: Hour 6:00PM Day 11th Month Jan. Year 1966

The Above well was plugged as follows:

Circulation was lost drilling the surface hole on this well, from 665' to 750' is the lost circulation area. Hole was dry drilled to 915'.

913' of 8 5/8" surface pipe was run in the hole, and bottom of pipe was cemented with 250 sacks to the lost circulation area at 750'.

Several attempts were made to cement the pipe, from the top of the lost circulation area to the base of the cellar, but failed. Hole was abandoned. 370' of 8 5/8" surface pipe was recovered from the hole.

Static fluid level in the hole was at 200', bridge plug was pushed in fluid to 300', and cemented with 30 sacks, through the drill pipe. Bridge plug was set at 40', hull bridge from 40' to 25', and cemented with 20 sacks to the

I hereby certify that the above well was plugged as herein stated.
base of the cellar.

INVOICEDSigned: Archie Elving
Well Plugging SupervisorDATE 1/13/66INV. NO. 2592-W