

DISTRICT CONSERVATION AGENT'S REPORT

CR3 R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. SW NE SE

LOCATION Sec 14

SEC. 8 TWP. 31 RGE. 14W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Mills

Operator J. M. Huber, Cochr Address Box # 460 Pratt-Kans

Field _____ County Barber

Total Depth 4496 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 16" - 124' ft. Circulated with cement
10 3/4" - 800' ft. Circulated with cement.
5/8" casing set at 4449' ft. - 250 sacks of cement.
Plugged back to 3578' ft with mud-cement +
Lean Wells Plug - Filled hole with chat to 3575' ft
Dumped 50 sacks of cement at 3575' ft - Shot off & killed
the 5/8" casing mud to 275' ft. Set Rock Bridges & 20 sacks
of cement at 275' ft - mud to 34' ft - Bridges &
10 sacks of cement at the surface

RECEIVED
STATE CORPORATION COMMISSION
9-22-51
SEP 22 1951
PLUGGING DIVISION
WICHITA, KANSAS
FILE SEC. 8 TWP. 31 R. 14W
BOOK PAGE 111 LINE 15

C. R. Stoen
District Conservation Agent
Date 9-20-51