

DISTRICT CONSERVATION AGENT'S REPORT

*Handwritten initials and a large scribble.*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. NE SE SE

LOCATION NE-SW-SW

SEC. 8 TWP. 31 RGE. 14-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Mills

Operator J. M. Huber Corp Address Box #460 Pratt-Kans

Field \_\_\_\_\_ County Barber

Total Depth 4370 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 15 1/2 - 115 ft. Circulated with cement.  
10 3/4 - 800 ft. Circulated with cement - 5 1/2 casing set  
at 4350 ft. Cemented with 125 sacks of cement - Plugged  
back with shot to 4330 ft. - Pumped 5 sacks of cement at 4330 ft.  
Shot & pulled the 5 1/2 casing - mud to 275 ft.  
Set Rock Bridge & 20 sacks of cement at 275 ft.  
mud to 35 ft. - Bridge & 10 sacks of cement  
at the surface.

REC'D  
STATE CORP COM

**PLUGGING**  
FILE SEC 8 1 31 R 14  
BOOK PAGE 138 LINE 33

JAN 18 1952  
18-82

C. N. Stough  
District Conservation Agent

Date 1-15-52