

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1965
2-19-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Hinkle Oil Company

Complete Address: 1016 Union Center, Wichita, Kansas

Lease Name Shaft Well No. # 1

Location SW SE SW Sec. 18 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4804'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 6:00PM Day 17th Month Feb. Year 1965

The Above well was plugged as follows:

898' of 8 5/8" surface pipe, cement circulated. 4801' of 5 1/2" long
string, cemented with 150 sacks. Bottom plug was pushed to 4670', and
20' of sand, and cemented with 5 sacks. 3601' of 5 1/2" long string was
recovered from the hole. Fluid level in the hole was now at 300'.
Bridge plug was set on fluid at 300', and 10' of rock bridge, and
cemented with 25 sacks. Hole was filled with mud to 40', and 10' of
rock bridge, and cemented with 10 sacks to the base of the cellar.

I hereby certify, that the above well was plugged as herein stated.

DATE 2/19/65
INV. NO. 406-u

Signed: Archie Elving
Well Plugging Supervisor