

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 4 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sinclair Oil & Gas Company

Complete Address: P. O. Box 521, Tulsa 2, Oklahoma

Lease Name W. A. Newkirk Well No. # 10

Location SW SW Sec. 8 Twp. 33 Rge. 11 (E) (W)W

County Barber Total Depth 4525

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 7:30PM Day 1st Month May Year 1964

The Above well was plugged as follows:

235' of 10 3/4" surface pipe, cement circulated. 4523' of 5 1/2" long string, cement-
ed with 250 sacks. Plug back to 4486'. Top perforation 3626'. Bottom hole plug was
pushed to 3360', and 20' of sand, cemented with 5 sacks. Pipe was shot off at 3200'
Hole was gassy. 70 sacks of Gel-Mud was pumped into 5 1/2", to break circulation, but
failed. Top of Fort Riley was 2540'. Pipe was pulled up to 2600', and cemented with
75 sacks, through 5 1/2" swage. Hole was still gassy. Hole was squeezed with 20 sacks
of Gel-Mud and 150 sacks of cement, through a 10 3/4" swage, into surface pipe, to
a pressure of 200 lbs. Plug on top of cement was pumped down to 150', with water,
to a pressure of 450 lbs. Surface pipe was capped with 5 sacks of cement. This cem-
enting was done by Halliburton Cementing Co. 3200' of 5 1/2" long string was recovered
from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/5/64
INV. NO. 9094-U

Signed: Archie Elving
Well Plugging Supervisor