

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

*CPB R*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 73-10 County: Butler

Location: SW NW SW Sec. 24 Twp. 33 Rge. 11 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 4632

I have this date completed supervision of plugging of:

Lease Name: Circle Well No. 2

Operator's Full Name: Simclair Oil & Gas Co.

Complete Address: Box 551, Chase, Kans.

Plugging Contractor: West Supply Co.

Address: Chase, Kans.

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No \_\_\_\_\_

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3:30 PM Day 8 Month April Year 1959

The above well was plugged as follows:

*240' of 10 3/4" surface casing acutated with 175 5X cont - Top  
Casing at 4552' - PBTD 4599' - Hole was cased to 4544'  
and 5 sack cement dumped with dump bucket - Production  
pips pulled. Hole mudded to 235' - 10' Rock Bridge from  
235' - 225' - 25 sack cement dumped top bridge - Mudd  
to 40' - Rock bridge from 40' - 30' with 15 5X cont  
poured top bridge.*

Signed: *W. H. Kump*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 14 T 33 R 11W  
BOOK PAGE 23 LINE 10