

KANSAS

FORM CP-3  
Rev. 11-3-80

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT REPORT

15-007-01371-00-00

API Number 15- - none ✓

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Isern-Schultz Oil &amp; Gas Inc.

Complete Address Box 486 Ellinwood, Kansas 67526

Lease Name Newkirk "B" Well No. 1

Location SW NW SE Sec. 31 Twp. 33 Rge. 11W (East) (West)

County Barber Total Depth 4720'

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☐

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address Shown above License No. 868

Operation Completed: Hour: 12<sup>00</sup> Noon Day: 28 Month: 4 Year: 19 81

The above well was plugged as follows:

5½" 4710' W/125 sx

252' 8 5/8" W/20 sx

Perf top 4564-4639 Sand back to 4500' W/5 sx cement

Squeezed W/ 15 gel 8 hulls 10 gel Released plug &amp; displaced

W/ 125 sx 50/50 pozmix 4% gel 3% C.C. SIP 700 #

Cemented by Sun Rec-2517'

RECEIVED

STATE CORPORATION COMMISSION

MAY - 4 1981

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. W. Dashi  
Conservation Division Agent

DATE 5-28-81

INV. NO. 5506-W