

State of Kansas



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 18 December, 19 58, authorized the following plugging operation:

Operator's Full Name: Barbara Oil Co.

Complete Address: 322 Central Bldg., Wichita, Kans.

Lease Name: Forester "C" Well No. 1

Location: CS/2 NW Sec. 27 Twp. 33 Rge. 11 (E) (W) X

County: Barber Total Depth: 4630

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

209' of 8 5/8" surface casing circulated with cement. Fill hole
with heavy drilling mud to 200'. Set cementing plug at 200' with
20 sack cement top plug through drill pipe. Heavy mud to 35'.
Set cementing plug at 35' with cement to base of cellar.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 24 1958

CONSERVATION DIVISION

Very truly yours,

Signed: [Signature]

Conservation Division Agent