

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Kansas

Lease Name Bryant Well No. # 1

Location NE SW SE Sec. 27 Twp. 33 Rge. 11 (E) (W)W

County Barber Total Depth 4625

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: E. K. Edmiston Drilling Company

Address: 501 First National Bank Bldg., Wichita, Ks. License No.

Operation Completed: Hour 1:30AM Day 27th Month July Year 1964

The Above well was plugged as follows:

238' of 8 5/8" surface pipe, cemented with 175 sacks. Hole was filled
with drilling mud to 235', 1st cementing plug, bridged solid with hulls,
on fluid at 235', and cemented with 25 sacks. Hole was filled with drill-
ing mud to 40', 2nd cementing plug, bridged solid with hulls, on fluid
at 40', and cemented with 10 sacks to base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/29/64
INV. NO. 9558-4

Signed: Archie Elving
Well Plugging Supervisor