

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1965

5-3-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2; Kansas

Operator's Full Name Ferguson Oil Company

Complete Address: 522 Union Center Bldg., Wichita, Kansas

Lease Name Werner-Lambert Well No. # 1

Location NE NW SE Sec. 29 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4540'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was washed down

Plugging Contractor: Walters Drilling Company

Address: 510 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 3:30PM Day 30th Month April Year 1965

The Above well was plugged as follows:

794' of 8 5/8" surface pipe, cement circulated with 350 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged
solid with hulls on fluid at 300', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 5/3/65
INV. NO. 1086-4

Signed: Archie Elving
Well Plugging Supervisor