

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials and signature: CRB

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 56-4

LOCATION NE-NE-NE

SEC. 18 TWP. 31 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Oldfather

Operator Champion Refining Co Address Box #452 Prud. Okla

Field _____ County Barber

Total Depth 4510 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 750 ft. Circulated with cement.
5 1/2" casing set at 4510 ft. Cemented with 300 sacks cement.
Lave Wells Plug at 4450 ft. Filled hole with chat
from 4450 to 4335 ft. - Pumped 5 sacks of cement at 4335 ft.
Shot off & pulled the 5 1/2" casing - mud to 2750. Set
Rock Bridge & 20 sacks of cement at 2750 - Mud to
30 ft. Plug & 10 sacks cement at the surface -
Pipe Pulling, Inc. Plugging Contractors*

PLUGGING
FILE SEC 18 T 31 R 14W
BOOK PAGE 56 LINE 4

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1951
CONSERVATION DIVISION
District Conservation Agent

Date 1-25-51