

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials and signature: CB and a large stylized signature.

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 27-7

LOCATION NE 7E-SE

SEC. 18 TWP. 31 RGE. 14-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Oldfather

Operator Springer & Southern Address #402 N. N. Bldg. Wichita-Kans.

Field \_\_\_\_\_ County Barber

Total Depth 4481.75 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 875 ft - Circulated with cement.  
5/8" casing set at 4428.75 - Cemented with 175 sacks cement.  
Plugged back to 4415 ft - with shot - Dumped 6 sacks  
of cement at 4415 ft - Shot off & pulled the 5/8" casing  
filled with mud to 250 ft - Set Rock Bridge &  
20 sacks of cement at 250 ft - Mud to 30 ft  
Plug & 10 sacks of cement at the surface -  
Bob Mullins - Plugging - Contractor

RECEIVED  
STATE CORPORATION COMMISSION  
10-5-50  
OCT 5 - 1950

CONSERVATION DIVISION  
District Conservation Agent W. Stough

**PLUGGING**  
FILE SEC 18 T 31 R 14W  
BOOK PAGE 27 LINE 2

Date 10-2-50