

15-007-10082-0000

P

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1973  
11-12-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Raymond Oil Co.  
Complete Address 200 W Douglas Wichita, KS  
Lease Name Shaft A Well No. 1  
Location C NW/SE Sec. 18 Twp 31 Rge. 14 (E)     (W) W  
County Barber Total Depth 4 605  
Abandoned Oil Well X Gas Well     Input Well     SWD Well     D & A      
Other well as hereafter indicated      
Plugging Contractor Knight Casing Pulling Co Inc  
Address Box 405 Chase, KS License No. 436  
Operation Completed: Hour 11:00 AM Day 10 Month 11 Year 1973

The above well was plugged as follows:

218 ft 133/8 surface cement circulated. 1720 ft 8 5/8 cemented with  
150 sacks. 4600 ft 5 1/2 long string cemented with 100 sacks. Top  
perf. 4479 ft. Sand to 4400 ft. 5 sacks cement with bailer. Pulled  
2820 ft 5 1/2/ Set 20 ft rock bridge at 460 ft. Fill hole with 7 yds  
redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 11/12/73

INV. NO. 8158-W