

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1973  
11-12-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Raymond Oil Co

Complete Address 200 W Douglas Wichita, KS

Lease Name Shaft Well No. 2

Location 50' E/C/ N/2 Sec. 18 Twp. 31 Rge. 14 (E) (W)

County Barber Total Depth 3944

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 4:00 PM Day 10 Month 11 Year 1973

The above well was plugged as follows:

200 ft 133/8 surface cemented with 225 sacks. 3940 ft 5 1/2 long string  
cemented with 175 sacks. Top perf. 3781 ft. Sand to 3700 ft, 5  
sacks cement with bailer. Pulled 1900 ft 5 1/2. Set 20 ft rock bridge  
at 160 ft. Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 11/12/73

INV. NO. 8157-W